

Project ID	CN	Project Number	Project Name	Roadway Summary	Bridge Summary <i>*CBCs noted as UIP may require extension</i>	FY	Letting***	Estimate (Millions)	Design Manager	Planning	Survey	Env	RDD	Bridge	Bridge H&H	ROW Survey	ROW Design	Public Inv.
1	13500	NH-6-6(166)	Sun Valley Blvd over UPRR	Approach work necessary for bridge replacement ** Project schedule to be further assessed based on preliminary analysis.	1 bridge replacement over railroad Hydraulic modeling may be required	TBD**	TBD**	\$4.42	Keller	N	N	Y	Y	Y	Y	N	N	Y
2	13534	STP-103-2(105)	Cheese Creek Bridge	Supporting activities for bridge repairs	1 bridge size structure repair and scour mitigation **Floodplain certification only	2024	8/24/2023	\$0.36	Keller	N	Y	Y	Y	Y	Y**	N	N	Y
3	13536	STP-62-7(112)	Elk Creek East Bridge	Supporting activities for pile repair	Repair pile due to deterioration	2024	8/24/2023	\$1.01	Keller	N	Y	Y	Y	Y	N	N	N	Y
4	22578	NH-275-7(196)	W Branch Papillion Creek West, Omaha	Mill and resurface roadway and shoulders, ADA curb ramp modifications	None	2026	8/28/2025	\$1.96	Hale	N	N	Y	Y	N	N	N	N	Y
5	22852	NH-680-9(52)	Pacific- Dodge, Omaha	Construct additional lane on NB and SB I-680 **Note: Non-traditional survey methods may be required	2 bridge size structures: 1 repair, 1 widen and repair (NB direction only) Hydraulic modeling required	2026	8/28/2025	\$5.62	Hale	N	Y**	Y	Y	Y	Y	Y	N	Y
6	22866	NH-75-2(189)	Chandler Road - F Street, Omaha	Construct additional NB driving lane, mill and resurface roadway and shoulders, curb and flume, culverts	4 bridge size structures: 2 repairs and 2 replace	2025	8/29/2024	\$10.96	Hale	N	N	Y	Y	Y	N	Y	Y	Y
7	22872	NH-680-9(54)	I-680 & US-6 Interchange	Expand NB to WB ramp to 3 lanes and construct dedicated ramp for SB I-680 to US-6 (lower roadway)	1 bridge repair and widening	2026	8/28/2025	\$4.64	Hale	N	N	Y	Y	Y	N	Y	Y	Y
8	22888	HSIP-275-7(209)	US-275 & W Dodge Rd, Omaha	Intersection modification	None	2026	11/6/2025	\$3.86	Hale	N	Y	Y	Y	N	N	N	N	Y
9	42778	STP-4-5(106)	Davenport West	Mill and resurface roadway, guardrail, culverts	2 bridge size structures: 1 UIP (CBC), 1 bridge repair **Floodplain certification only	2025	8/29/2024	\$4.62	Kessler	N	N	N	Y	Y	Y**	N	N	Y
10	42874	STP-10-2(124)	Pleasanton - Hazard	Mill and resurface roadway and shoulders, trench widening, culverts, guardrail	5 bridge size structures: 3 UIP (CBC), 2 bridge repairs **Floodplain certification only	2025	8/29/2024	\$6.23	Kessler	N	N	N	Y	Y	Y**	Y	Y	Y
11	42875	STP-4-5(107)	Davenport East	Asphalt and concrete repair, mill and resurface roadway, guardrail, culverts	5 bridge size structures: 3 UIP (CBC), 2 repairs **Floodplain certification only	2025	8/29/2024	\$5.33	Kessler	N	N	N	Y	Y	Y**	N	N	Y

***All project schedules are subject to change following NDOT's annual program assessment, which will occur late 2022/early 2023. PS&E dates typically occur 4 months in advance of the scheduled letting.

Project ID	CN	Project Number	Project Name	Roadway Summary	Bridge Summary <i>*CBCs noted as UIP may require extension</i>	FY	Letting***	Estimate (Millions)	Design Manager	Planning	Survey	Env	RDD	Bridge	Bridge H&H	ROW Survey	ROW Design	Public Inv.
12	42898	STP-183-2(111)	Elm Creek - Miller	Mill and resurface roadway, add surfaced shoulders, culverts, guardrail	3 bridge size structures: 1 UIP (CBC), 2 repairs Scour mitigation analysis required	2025	8/29/2024	\$14.18	Kessler	N	N	N	Y	Y	Y	Y	Y	Y
13	42899	STP-183-2(112)	Miller - Buffalo/Custer Co Line	Mill and resurface roadway and shoulders, guardrail, culverts	5 bridge size structures: 2 UIP (CBC), 3 repairs **Floodplain certification only	2025	8/29/2024	\$7.98	Kessler	N	N	Y	Y	Y	Y**	Y	Y	Y
14	42925	STP-40-4(105)	Amherst - N-10	Mill and resurface roadway, guardrail, culverts	9 bridge size structures: 8 UIP (CBC), 1 bridge repair **Floodplain certification only	2025	8/29/2024	\$5.46	Kessler	N	N	N	Y	Y	Y**	N	N	Y
15	42935	NH-STP-6-4(132)	Hastings West	Concrete repairs, mill and resurface roadway and shoulders, guardrail, lighting	2 bridge size structures: 1 repair, 1 replace	2025	8/29/2024	\$8.12	Kessler	N	Y	N	Y	Y	N	Y	N	Y
16	51191	STP-250-4(102)	Lakeside North	Mill and resurface roadway, trench widening, culverts	None	2026	8/28/2025	\$3.55	Hale	N	Y	N	Y	N	N	N	N	Y
17	51193	STP-250-4(104)	Smith Lake North	Mill and resurface roadway, trench widening, culverts	None	2026	8/28/2025	\$6.77	Hale	N	Y	N	Y	N	N	Y	N	Y
18	51635	NH-STP-26-1(178)	In Scottsbluff	US-26, N-71, N-92, S-79H: concrete and asphalt repairs, mill and resurface	3 bridge repairs **Floodplain certification only	2025	12/19/2024	\$9.03	Hale	N	Y	Y	Y	Y	Y**	N	N	Y
19	51640	STP-27-4(113)	Niobrara River South	Mill and resurface roadway, trench widening, culverts	None	2025	8/29/2024	\$8.79	Hale	N	N	N	Y	N	N	Y	N	Y
20	51642	NH-STP-26-1(177)	In Bridgeport	Concrete repairs, mill and resurface roadway, curb and gutter repairs	3 bridge size structures: 1 UIP (CBC), 1 redeck and repair, 1 repair **Floodplain certification only	2025	12/19/2024	\$1.74	Hale	N	N	Y	Y	Y	Y**	N	N	Y
21	51649	NH-71-3(129)	Harrisburg Spur North	Mill and resurface roadway, lighting, surface DMS pads and replace closure gates	5 bridge size structures: 1 UIP (CBC), 4 bridge repairs **Floodplain certification only	2026	8/28/2025	\$12.73	Hale	N	Y	Y	Y	Y	Y**	N	N	Y
22	51651	NH-385-2(115)	Sidney - Gurley	Mill and resurface roadway and shoulders, possible ADA and lighting modifications	3 bridge size structures: UIP (CBC) **Floodplain certification only	2026	8/28/2025	\$8.24	Hale	N	Y	Y	Y	N	Y**	N	N	Y
23	51655	STP-29-4(112)	Agate South	Mill and resurface roadway, trench widening	None	2026	8/28/2025	\$4.56	Hale	N	Y	Y	Y	N	N	Y	N	Y
24	61668	STP-HSIP-92-2(112)	Lemoyne East	Mill and resurface roadway, trench widening, curb and flume, culverts	None	2025	8/29/2024	\$4.43	Baird	N	N	Y	Y	N	N	Y	Y	Y

***All project schedules are subject to change following NDOT's annual program assessment, which will occur late 2022/early 2023. PS&E dates typically occur 4 months in advance of the scheduled letting.

Project ID	CN	Project Number	Project Name	Roadway Summary	Bridge Summary <i>*CBCs noted as UIP may require extension</i>	FY	Letting***	Estimate (Millions)	Design Manager	Planning	Survey	Env	RDD	Bridge	Bridge H&H	ROW Survey	ROW Design	Public Inv.
25	61673	STP-183-3(122)	Ansley South	Mill and resurface roadway, shoulder widening, culverts, guardrail	5 bridge size structures: 1 repair, 4 UIP (CBC) **Floodplain certification only	2025	8/29/2024	\$17.21	Baird	N	N	Y	Y	Y	Y**	N	N	Y
26	61686	STP-NH-30-2(151)	In North Platte	Concrete repairs, mill and resurface roadway and shoulders, guardrail, lighting	4 bridge size structures: 3 UIP (CBC), 1 repair **Floodplain certification only	2025	8/29/2024	\$4.32	Baird	N	N	Y	Y	Y	Y**	N	N	Y
27	61692	STP-30-3(119)	US-30 and US-283 In Lexington	Concrete repairs, mill and resurface roadway and shoulders, ADA curb ramps, lighting	None	2025	8/29/2024	\$2.59	Baird	N	N	Y	Y	N	N	N	N	Y
28	61727	NH-80-3(170)	Sutherland West I-80	Construct crossovers, remove and reconstruct roadway and shoulders **Note: Non-traditional survey methods may be required	4 bridge size structures: 2 UIP (County Road Overhead, CBC), 2 Replace	2025	8/28/2025	\$48.83	Baird	N	Y**	Y	Y	Y	N	N	N	Y
29	80952	STP-11-4(116)	Brush Creek - Niobrara River	Mill and resurface roadway, trench widening, culverts	1 bridge repair **Floodplain certification only	2024	8/24/2023	\$2.76	Kessler	N	N	Y	Y	Y	Y**	N	N	Y
30	81075	STP-97-4(115)	Valentine Southwest	Mill and resurface roadway, trench widening	None	2025	1/30/2025	\$3.31	Kessler	N	N	Y	Y	N	N	N	N	Y
31	81077	NH-20-2(149)	Fairfield Creek	Culvert replacement due to upstream flooding and head cutting	None **Floodplain certification only	2025	8/29/2024	\$0.27	Kessler	N	N	Y	Y	N	Y**	N	N	Y
32	81079	STP-183-4(120)	Springview South	Remove steel piling and install bank protection at upstream wing dikes **Note: Non-traditional survey methods may be required	No bridge size structures are part of this project but specialized hydraulic analysis for bank stabilization is required	2026	8/28/2025	\$0.59	Kessler	N	Y**	Y	Y	N	Y	N	N	Y
33	81089	STP-20-2(150)	Bryan Bridge	Approach work necessary for bridge rehabilitation	1 historic bridge rehabilitation Scour mitigation analysis required	2025	8/29/2024	\$1.98	Kessler	N	N	N	Y	Y	Y	N	N	Y
34	81094	NH-20-3(118)	Stuart West	Mill and resurface roadway and surfaced shoulders, culverts, guardrail	2 bridge size structures: 1 replace, 1 repair H&H analysis needed for bridge replacement	2025	8/29/2024	\$5.04	Kessler	N	N	N	Y	Y	Y	Y	N	Y
35	81095	STP-HSIP-12-4(114)	Butte - Spencer	Mill and resurface roadway, trench widening, culverts	None	2025	8/29/2024	\$4.87	Kessler	N	N	Y	Y	N	N	Y	N	Y

***All project schedules are subject to change following NDOT's annual program assessment, which will occur late 2022/early 2023. PS&E dates typically occur 4 months in advance of the scheduled letting.