

A. OVERVIEW

The consultant will provide Bridge related services for NDOT such as:

1. Preliminary Engineering Services including Bridge Data Sheet development and Type, Size, and Location plans (TS&L's)
2. Final Bridge Design
3. Bridge Plan production
4. Bridge Load Rating
5. Independent structural design reviews
6. Support in Value Engineering activities
7. Special design projects including, but not limited to, bridge repair and maintenance projects such as:
 - a. Joint replacements
 - b. Concrete repairs
 - c. Curb repairs
 - d. Bridge rail remodel
 - e. Bridge deck repairs
 - f. Bridge deck overlays
 - g. Superstructure and Substructure repairs
8. Construction phase services (future contract to begin at the start of construction) including but not limited to:
 - a. Calculating girder shims,
 - b. Shop drawing review
 - c. Providing construction consultation

B. QUALIFICATIONS, KNOWLEDGE AND EXPERIENCE

1. All work shall be completed by or under the direct supervision of a Nebraska licensed professional civil engineer. The consultant firm shall use engineers experienced with all aspects of bridge design related to the services to be provided.
2. The Consultant's team shall have working knowledge of and follow, when applicable:
 - a. Bridge design industry standards
 - b. The NDOT Bridge Office Policies and Procedures Manual. (BOPP)
 - c. AASHTO LRFD Bridge Design Specifications
 - d. NDOT Standard Specifications for Highway Construction
 - e. NDOT Approved Products List

- f. Special Provisions and Specifications developed by the NDOT's Bridge Division
 - g. Local, State and federal laws and regulations that pertain to bridge design
3. This is out of date. I would see what Roadway does and follow their lead. Reports and documents must be submitted in a form compatible with Microsoft Office products unless otherwise directed
 4. The Consultant will provide all software and computer equipment required to complete the work including any analysis software required to perform the bridge design work

C. EXPECTATIONS FOR THE DELIVERABLES

1. Plans and special provisions shall be developed in compliance with the manuals, guidelines and specifications as listed in the Qualifications, Knowledge and Experience section.
2. Bridge plans for new construction will typically be submitted to NDOT for review and comment at preliminary, 75% completion stage, 90% completion stage, and final. Bridge repair plans shall be submitted at 90% completion stage and 100% completion stage for review and comment. Final turn-in for all bridge projects shall include stamped and signed plans, preliminary unsigned plans for advertisement, all special provisions, and cost estimates (*for new and some rehab work new LRSS will need to be turned in as well*).
3. Plans will be completed and submitted in accordance with the schedule set out in the Task Orders. Occasionally, the NDOT may require the plans be completed on a "rush" basis for emergency repairs
4. Consultant's services will be used directly or incorporated into NDOT project plans for use in bidding and constructing projects