

## Tentative FY2027 State Surface Transportation Project List

Information is current as of 5/30/2025 and is subject to change

**DEPARTMENT OF TRANSPORTATION**

Control Number	Highway Number	Project Number	Project Location	Description of Work	Project Length	Asphalt (Tons)	Concrete (CY)	Status
11805	077	S-77-2(1082)	Wahoo East	Gr, Str, Conc Pvmnt 4-Lane Divided Expry With S-Shld	6.15	19,626	51,895	Design
12192	077	S-77-2(1085)	Fremont South	Gr, Str, Conc Pvmnt 4-Lane Divided Expry	4.81	21,600	70,316	Design
12552D*	077	S-77-2(1078)	Us-77/Pioneers Blvd Interchange	Interchange Reconstruction	0.80			Design
12598	080	NH-80-8(110)	Seward - Pleasant Dale	6-Lane Gr, Str, Conc Surf And Detour Work			17,004	Planning
12974	067	STP-67-2(110)	Lorton North & East	Mill, Resurf 24' Rdwy, Widen/Resurf Existing 22' Rdwy To 24', Br Repair/Overlay	6.32	22,701	122	Design
13294	Local	LCLC-5233(4)	33Rd/Cornhusker Viaduct, Lincoln	Viaduct Construction, Eliminate At Grade Crossings, Reconnect Affected Rdwys				Design
13306	008	STP-8-7(116)	Salem & Falls City Bridges	Br Replacements			5,692	Planning
13397	128	STP-128-7(110)	Lorton West	Mill, Widen/Resurf, Br Repair, Culvert	7.89	35,454	11	Design
13418	Local	LCLC-5275(2)	S 98Th St, 'A' St - 'O' St, Lincoln	New Roadway On New Alignment, Gr And Pvmnt For Urban Section And Drainage Str	1.01		6,173	Design
13434	Local	LCLC-5224(1)	Randolph St, Capitol Pkwy-40Th, Lincoln	Mill, Resurf, Pedestrian Ramps, Intersections	1.25	5,475	1,234	Design
13435	Local	LCLC-5213(3)	N 1St St/Cornhusker, Lincoln	Traffic Analysis, Traffic Signals	0.26		2,194	Design
13450	006	HSIP-5249(9)	84Th St And Us-6, Lincoln	Intersection Improvements	0.30		3,715	Design
13469	001	STP-HSIP-1-7(110)	Us-34 - Murdock	Mill, Resurf, 28' Widening, Br, Culvert	7.33	41,042	1,380	Design
13476	136	NH-136-6(131)	In Fairbury	Conc. Surf., Turn Lane			9,579	Planning
13478	050	STP-50-2(143)	In Syracuse	Mill, Resurf, Bridge Repair, Culvert	2.11	8,341		Design
13488	Local	TAP-FLTP-34(44)	Beatrice Homestead Trail	Construct A Hiking And Biking Trail			37	Design
13491	Local	LCLC-55(188)	Lincoln Area Bridges	Overlay, Membrane, Joint & Railing Repair On Bridges				Design
13492	5272	LCLC-5272(1)	Arbor Road Bridge	Replace Concrete Slab Bridge			868	Design
13493	Local	LCLC-3340(8)	Fletcher Ave, 84Th St To 148Th St	Resurface, Grading				Planning
13494	5287	LCLC-5287(1)	Nw 56Th St, I-80 To W. Holdrege St	Grading, Surface, Widen		7,887		Design
13495	Local	LCLC-5220(7)	A Street, 6Th To 17Th, Lincoln	Mill, Resurf, Pavmt Repair, Repair Pedestrian Ramps, Repair Inlet Tops, C&G				Design
13496	5206	LCLC-5206(2)	48Th & Calvert And 56Th & Calvert	Traffic Signal/Intersection Improvements			1,154	Design
13497	Local	LCLC-6-6(165)	Cornhusker Highway, 39Th To L55x	Mill, Resurf, Pavmt Repair, Repair Inlet Tops, C&G, Pedestrian Ramps, Signals	1.60	9,275		Design
13498	Local	LCLC-5237(4)	Cotner Blvd, O Street To Starr Street	Mill, Resurf, Pavmt Repair, Inlet Tops, C&G, Repair Pedestrian Ramps, Signals				Planning
13507	008	STP-8-7(117)	N-99 - Pawnee City	Mill, Overlay & Pcc Repair, Widening To 28'. Bridge Deck Repair And Ovly. Culvert		56,126	57	Design
13513	S66A	STP-S66A(106)	Douglas Spur	Mill And Resurface, Culvert Work, Bridge Repair		26,722	6	Planning
13515	034	HSIP-34-7(135)	Jct Us-34/N-50	Construction Of Roundabout To Improve Safety. Pvmnt Removal And Replacement, Gr.,	0.12		2,469	Design
13518	3265	LCLC-HSIP-3265(11)	68Th, Firth Rd To Stagecoach	Surfacing Widening, Sufaced Shoulders And Intersection Improvements	5.00	35,586		Design
13521	Local	BRO-7080(55)	Beaver Crossing Southeast	Bridge Replacement				Planning
13522	Local	BRO-7048(18)	Steele City West	Bridge Replacement				Design
13525	Local	BRO-7049(25)	Tecumseh Northwest	Bridge Replacement				Planning

## Tentative FY2027 State Surface Transportation Project List

Information is current as of 5/30/2025 and is subject to change

**DEPARTMENT OF TRANSPORTATION**

13526	Local	BRO-7074(26)	Stella Southwest	Bridge Replacement					Planning
13527	002	NH-2-7(123)	Lincoln - Syracuse	Penetrating Concrete Sealer And Seal Asphalt Shoulder To Conc. Mainline Joint					Planning
13548	Local	HSIP-5247(14)	70Th St & Nebraska Parkway, Lincoln	Right Turn Lane Addition, Grading, Widening, Pavement Replace, Traffic Signal	0.12		361		Design
13556	080	NH-80-8(169)	Goehner - Seward	Crack Seal					Planning
13563	080	ITS-NH-D1(108)	District 1 Dms Replacement	Replace Dms Board To Allow Full Color M Atrix Display					Planning
13598	Local	DPS-48(25)	Pwf Road	Pavement Removal, Grading, Culvert Remov AI, Bridge Deck, Girder Bridge					Planning
22795	066	STP-66-7(119)	N-66 Connection In Louisville	Build New Rdwy On Shifted Alignment And Bridge Spanning Floodway, Rr Xing	0.54	1,300	2,376		Design
22855	080	NH-MTIS-80-9(203)	50Th St- I-480, Omaha	Replace Pavement, Bridge & Culvert Work, Guardrail, Curb & Flume, Lighting	2.06	7,137	76,926		Design
22857	075	NH-75-2(187)	Hamilton St.-Fort St., Omaha	Crack Seal, Maintenance, Follow Up To Cn22647					Planning
22862	Local	TAP-77(64)	Gretna To Wehrspan Lake Trail	Construct Walking Trail					Planning
22873	370	TAP-370-7(133)	Hwy 370 Trail Underpass 114Th - 120Th	Trail					Planning
22884	Local	BRO-7013(17)	Louisville 6Th Street	Bridge Replacement					Planning
22910	480	NH-480-9(14)	I-480, N 20Th Street Sign Structure	Removal And Replacement Of Overhead Sign Sturcture	0.00				Design
22921	080	ITS-NH-D2(116)	District 2 Dms Retrofit	Retrofit 7 Dms Boards To Allow Full Color Matrix Displays					Planning
22922	080	ITS-NH-D2(117)	District 2 Dms Replacement	Replace Dms Structures At 11 Locations In District 2					Planning
22925	Local	TAP-27(72)	Fremont Fevr Rail To Trail	New Trail Construction					Planning
22932	Local	DPS-28(162)	24Th St Streetscape Improvement, Omaha	Restriping, Landscaping, Signage, Sidewalk Ramps, Sidewalk & Storm Sewer Mods					Planning
22934	Local	CMAQ-28(163)	Signal Infrastructure Phase E2	Upgrade Signal & Communication Infrastructures At 42 Signals					Planning
22935	Local	CMAQ-28(164)	Signal Infrastructure Phase F1	Upgrade Signal & Communication Infrstructure At 68 Signals					Planning
22948	Local	DPS-28(166)	Blackstone Streetscape Improvement, Omaha	Construct Sidewalks, Curb Ramps, Curbs, Gutters, Stripingg, Signage, Lighting					Planning
22950	080	MISC-80-9(1223)	I-80 Drainage At 96Th Street	Removing And Reconstructing The Failed Culvert And Inlet Structure					Design
22967	370	ITS-NH-D2(120)	District 2 & District 1 Fiber Cleanup	Complete Fiber Connections With District Highway Corridors					Planning
22980	080	NH-80-9(216)	Wb I-80 Bridge At I-680	Bridge Overlay & Joint Repair		701	282		Planning
22983	Local	MAPA-5081(3)	Bellevue Major Street Resurfacing	Mill, Asphalt Resurface					Planning
22991	Local	MAPA-28(174)	Omaha Major Street Resurfacing	Resurfacing Project To Remove Roadway Deficiencies On Omaha's Major Streets					Planning
32356	020	NH-20-7(117)	Jackson - N-110	Mill, Resurf	3.16	14,735			Design
32381	275	NH-275-5(146)	Neligh To Tilden	Resurface, Bridge And Culvert Work	12.40	54,381	1,410		Design
32382	012	STP-HSIP-12-6(120)	Fordyce East & West	Resurface, Widening, Bridge And Culvert Work	9.20	37,808	74		Design
32383	014	STP-14-4(119)	Elgin - Neligh	Resurface Roadway And Shoulders, Bridge And Culvert Work	10.90	58,378	255		Design
32387	275	NH-275-5(147)	Clearwater West	Resurface Roadway And Shoulders, Culvert Work	6.49	33,807			Design
32402	035	NH-STP-35-4(129)	In Wayne	Crack And Joint Sealing, Lighting Upgrades, Concrete Repair					Planning

## Tentative FY2027 State Surface Transportation Project List

Information is current as of 5/30/2025 and is subject to change

**DEPARTMENT OF TRANSPORTATION**

32409	081	HSIP-81-4(130)	Jct. Us-81/ N-12 Intersection	Intersection Improvements And Culvert Work			2,618		Design
32419	129	NH-129-1(33)	South Sioux City West	Crack Seal					Planning
32435	081	NH-81-3(152)	In Norfolk - Pasewalk Avenue North	Resurf, Ada Ramps, Curbs		9,257			Planning
42013	014	RRZ-TMT-14-2(123)	Central City Viaduct	New Viaduct, 24' Conc Pvmnt W/8' Shld, 44' B-B Urban Section	0.72	1,108	26,524		Design
42777	002	STP-2-5(103)	Us-34 - W Jct I-80	Resurf	3.26	17,005			Design
42778	004	STP-4-5(106)	Davenport West	Resurf, Br	12.90	42,561	164		Design
42891	n/a	MISC-40(65)	District 4 Wetland Bank	Survey, Design, Construct And Monitor A Wetland Mitigation Site					Design
42899	183	STP-183-2(112)	Miller - Buffalo/Custer Co Line	Resurf, Br		38,569	89		Design
42924	040	STP-40-4(104)	Miller - Amherst	Resurf, Bridge Replacement		41,464	414		Planning
42925	040	STP-40-4(105)	Amherst - N-10	Resurf, Bridge Work	11.74	57,073	3		Design
42931	081	NH-81-2(151)	Stromsburg South	Resurf	6.52	31,166	220		Design
42937	006	NH-6-4(134)	Hastings East	Resurf	35.32	38,069			Design
42944	034	NH-34-4(136)	Doniphan - I-80	Resurf, Bridge Work	3.36	30,077	245		Design
42945	014	STP-14-1(125)	Nelson North	Resurfacing And Pavement Repair Of Surfaced Shoulders, Br	11.20	34,444	11,894		Design
42947	081	NH-81-1(126)	Bruning North And South	Resurface, Culverts, Bridge Repairs	10.04	75,394	11		Design
42949	080	NH-STP-80-8(168)	Waco To Utica	Crack Seal Project, Bridge Work					Planning
42950	080	NH-80-5(87)	Odessa To Kearney Wb	Joint Sealing Project (Wb Only)					Planning
42955	030	STP-30-4(165)	In Kearney West Of Unk	Reconstruction (4-Lane)	1.58		15,578		Design
42963	092	STP-92-5(111)	Platte River West	Resurfacing	3.17	14,900			Design
42979	081	NH-STP-81-1(127)	Kansas Line - Hebron South	Concrete Pavement Repair, Bridge Repair, Dowl Bar Retrofit, Weigh Station Ramps		94			Planning
42982	080	NH-80-7(172)	West Of Aurora - Henderson	Crack Seal					Planning
42983	080	NH-80-6(122)	Shelton - N-11 Jct.	Crack Seal					Planning
43010	Local	DPS-93(15)	Project Access York	Build Pedestrian Infrustructure For York That Has Ped Overpass And Trail			575		Design
43016	080	NH-80-7(176)	Giltner East	Crack Seal					Planning
43023	080	NH-80-7(178)	Platte River - Phillips (Resurf)	Resurface, Bridge Repair		75,925	176		Planning
43026	080	ITS-NH-STP-D4(109)	District 4 Dms Retrofit	Removal Of Existing & Install New Dms Panels					Planning
43028	Local	TAP-40(70)	Grand Island West Connector Trail	Bikeway/Trail					Design
51193	250	STP-250-4(104)	Smith Lake North	Asph Resurf/Widen 24' Rdwy To 28' W/2' Earth Shld, Culvert Work	11.10	20,935			Design
51521B	026	NH-26-1(182)	Minatare - Us-385, Phase 2	Construct New Lanes, Grading, Culvert Extension, Resurfacing Existing Lanes		42,307	106,883		Design
51651	385	NH-385-2(115)	Sidney - Gurley	Mill And Resurface Roadway And Shoulders, Curb Ramps	12.55	64,312	304		Design
51657	385	NH-385-4(141)	Chadron North	Upgrade Roadway To Super 2, Subgrade, Shoulder Repairs, Resurface		132,141	3		Design
51671	030	STP-30-1(141)	Sidney - Lodgepole	Resurface, Curb Ramps, Bridge Work, Shoulder Widening, Culvert Work		78,707	744		Planning
61360	083	NH-83-2(129)	Leota - 1St St (Nb), North Platte	Urban Reconstruction, Storm Sewer And Lighting	1.07		8,760		Design

DEPARTMENT OF TRANSPORTATION

Information is current as of 5/30/2025 and is subject to change

61632A	030	STP-NH-30-2(150)	In Ogallala	Replace Concrete Pavement, New Curb & Gutter, Joint & Crack Seal					Design
61648	S56A	STP-S56A(107)	Maxwell South	Mill, Resurf, Br	2.10	5,260	2,313		Design
61703	002	NH-STP-2-3(130)	Berwyn - Ansley	Conc Repair, Resurface, Bridge Work		8,466	216		Planning
61733	283	STP-283-2(108)	In Lexington South	Concrete Repairs And Resurfacing (Asphalt), Bridge Work	2.48	20,674			Design
61740	080	NH-80-3(174)	Hershey East, I-80 (Resurf)	Mill 4"/ Fill 4" Asphalt Overlay	9.94	87,155			Design
61742	080	ITS-NH-D6(110)	District 6- Dms Retrofit	Upgrade The Display Matrices On Dms Signs To Full Color Displays					Planning
61767	083	ITS-NH-83-2(145)	D6 Fiber Connectivity	Create Fiber Connections And Connect Fiber For Signal Cabinents					Planning
71225	006	STP-6-2(133)	Imperial - Enders	Resurface	8.62	49,170			Design
71250	061	STP-61-1(113)	Dundy/Chase Co Line N & S	Resurface	8.36	26,927			Design
71256	006	NH-6-2(136)	Jct. Us-34 - Mccook	Resurface, Bridge Work	13.60	68,992	1,340		Design
71266	083	NH-83-1(122)	Mccook South	Resurface, Bridge Work	6.90	41,965	273		Design
71267	083	NH-83-1(123)	Jct N-89 North & South	Resurface	6.90	34,377	9		Design
71270	044	STP-44-1(107)	Us-6 - Platte River	Resurface, Bridge Work		58,939	1		Design
80617	097	STP-97-4(109)	Merritt Reservoir South	Asph Widen/Resurf 22' Rdwy To 28' W/4' Earth Shld	7.64	50,674	186		Design
81060	007	STP-7-4(123)	Calamus River - Ainsworth	Microsurfacing					Planning
81061	012	STP-12-4(113)	Springview Area	Microsurfacing					Planning
81062	083	NH-83-4(122)	Valentine South	Microsurfacing					Planning
81065	012	STP-NH-12-4(112)	Spencer Area	Microsurfacing					Planning
81113	281	NH-281-4(133)	O'neill North	Resurface Driving Lanes And Shoulders	13.06	68,788			Design
81114	083	NH-83-4(124)	S-16B-Us-20	Resurface Driving Lanes And Shoulders, Bridge Work	10.27	46,984			Design
81117	020	NH-20-3(119)	Johnstown- Ainsworth	Resurface Driving Lanes And Shoulders	9.29	50,022			Design
81151	183	ITS-NH-STP-D8(105)	District 8 Cameras & Rwis Replacement	Install New Or Replace Highway Cameras, Towers, And Rwis As Needed					Planning
<b>Total Quantities</b>						<b>1,961,983</b>	<b>435,132</b>		

**Disclaimers:**

- Information is current as of 5/30/2025 and is subject to change
- Project list and quantities will be updated annually  
<http://dot.nebraska.gov/business-center/business-opp/hwy-bridge-lp/upcoming-projects/>

**Description of Work Abbreviations:**

- Conc (Concrete)
- S. Shld. (Surfaced Shoulders)
- Culv (Culvert) - An existing bridge is planned to be replaced with a culvert
- Br. (Bridge) - New construction, reconstruction, widening, or rehabilitation of an existing bridge and/or approach
- Resurf (Resurfacing) - Additional layer of surfacing material placed on top of existing surface
- Urban - Construction of divided or undivided curbed roadway in an urban area. May include grading, structure, and incidental work

**Quantity Notes:**

- Estimates are rounded
  - Status indicates the level of project information available at the time the quantities were calculated
    - Planning (5-15%), Design (15-90%), PS&E (90+%)
  - If no quantities are displayed, they were not available at the time this list was published or are not applicable
  - Concrete Repair quantities are not included
  - Niobrara East/West quantities are not included
- \*Carryover-project funded in previous fiscal year(s).