RFQ-2326 Multi-Service Project List

Attachment A

ID	CN	Project Number	Project Name	Roadway Summary	Bridge Summary	FY	Letting	Total Estimate (Millions)	Design Manager	Plannin g	Survey	Env	RDD	Bridge	Bridge H&H	ROW Survey	ROW Design	Public Inv.
1	12046		Hwy 6 & Adams St Bridges over I-180	and sidewalk as necessary for	2 bridge size structures: repalce with no grade raise. Detour may be required for one structure. Floodplain certifications are needed for the bridge work.	26	10/2/2025	\$3.94	Keller	Z	N	Υ	Υ	Y	N	Z	Z	Υ
2	13472	NH-180-9(8)	I-180 Bridges over I-80	Approach work necessary for bridge replacements, guardrail	2 bridge size structures: replace; grade raise required for both structures. No floodplain certifications needed for the bridge work.	27	8/27/2026	\$8.74	Keller	N	N	Υ	Υ	Υ	N	N	N	Y
3	13487	I NIH /6 1/11/11	US-75, Kansas State Line-Auburn	Mill and resurface nearly 27 miles of roadway, culverts, grading, guardrail	9 bridge size structures: 6 repair and overlay (minor grade raise), 1 replace (minor grade raise), 1 CBC repair with sheet pile wall, 1 UIP or extend as needed (CBC). Floodplain certifications are needed for the bridge work.	26	3/5/2026	\$21.66	Keller	N	N	Υ	Υ	Y	Y	Y	N	Y
4	32393	NH-81-4(129)	N-59 - N-84	US-81: Concrete patching and resurface. N-84: Resurfacing	6 bridge size structures: 2 replacements (minor grade raise), 1 repair and overlay (minor grade raise), 3 UIP or extended as needed (CBC). Floodplain certifications are needed for the bridge work.	26	8/25/2025	\$7.64	McCullough	N	N	N	Υ	Υ	Y	N	Z	N
5	42944	NH-34-4(136)	Doniphan to I-80	Mill and resurface roadway, guardrail, lighting	5 bridge size structures: 5 repair and overlay (minor grade raise). Floodplain certifications are needed for the bridge work.	27	8/27/2026	\$6.97	Ataullah	N	N	N	Υ	Υ	N	N	N	N
6	42945	STP-14-1(125)	Nelson North	additional short segment on N-4	4 bridge size structures: 2 replace, 1 replace with CBC, 1 repair and overlay (minor grade raise). Floodplain certifications are needed for the bridge work.	26	8/25/2025	\$11.45	Ataullah	Z	N	Z	Y	Y	Y	Y	Z	N
7	61726	NH-80-4(161)	Maxwell - Brady	Remove and reconstruct roadway and shoulders	3 bridge size structures: 1 repair, 2 UIP. No floodplain certifications are needed for the bridge work.	27	7/23/2026	\$66.90	McCullough	N	Υ	Υ	Υ	Υ	N	N	N	N
8	81137	NH-20-2(155)	Thatcher - Arabia	Mill and resurface roadway	No bridge size structures	27	8/27/2026	\$5.11	Ataullah	N	Υ	Y	Υ	N	N	N	N	N

^{***}All project schedules are subject to change. PS&E dates typically occur four months in advance of the scheduled letting.