

US-34 North & South, Seward

STP-15-2(117); C.N. 12080

PRE-CONSTRUCTION PUBLIC INFORMATION MEETING

TUESDAY, MARCH 19, 2024 | LIED SENIOR CENTER | 1010 MANOR DRIVE, SEWARD, NE 68434

LOCATION ► Identified as **US-34 North & South, Seward**, the project will reconstruct approximately 1.1 miles and resurface 0.4 miles of Nebraska Highway 15 (N-15). The reconstruction segment will build a new concrete roadway starting just south of the Burlington Northern Santa Fe Railroad crossing at mile marker (MM) 66.22 and extend north to MM 67.32 just beyond the intersection of N-15 and North Avenue. The resurfacing segment will overlay the roadway with asphalt from the reconstruction section (MM 67.32) to just north of Pinewood Avenue (MM 67.69).

IMPROVEMENTS ► Construction in the reconstruction segment will consist of removing the existing pavement and replacing it with doweled concrete pavement with integral curb, reconstructing curb inlets and storm sewer, reconstructing pedestrian facilities, and updating/replacing roadway lighting and traffic signals. Existing utilities will be reconstructed or relocated as needed. Work will include a two-way left turn lane from Jackson Avenue to North Avenue, reconstruction of driveways and intersections on N-15. Construction in the resurfacing segment will consist of concrete pavement repairs and resurfacing the roadway and surfaced shoulders where present. Additional work will include sidewalk Americans with Disabilities Act (ADA) improvements and widening the roadway to accommodate the northbound right-turn lane at Northern Heights Drive.

CONSTRUCTION TIMELINE ▼

Anticipated Construction Start Early April 2024

PHASE 1

Dollar General to US-34 Spring/Summer 2024

PHASE 2

Southbound lane US-34 to Jackson Ave Spring/Summer 2024

Northbound lane US-34 to Jackson Ave Spring/Summer 2024

Normal two-lane traffic will resume July 1 to July 5, 2024

Asphalt Overlay North Ave past Pinewood Ave Summer 2024

Southbound lane Park Ave to North Ave Summer 2024

Southbound lane Jackson Ave to Park Ave Summer 2024

Northbound lane Park Ave to North Ave Fall 2024

Northbound lane Jackson Ave to Park Ave Fall 2024

Anticipated Construction End
(seed, sod and general clean up) Spring 2025

Dates shown are approximate and may vary based on weather and other unforeseen conditions.



TRAFFIC IMPACTS

Work will be completed in phases with segments closed and traffic detoured during construction.



PEDESTRIAN IMPACTS

Work on sidewalks will be completed in phases with segments temporarily closed and pedestrians detoured. Pedestrian access to adjacent businesses will be maintained.



CONTRACTED AMOUNT

(construction costs only)

\$9.9 Million

Constructors, Inc.
was awarded the contract



PROJECT CONTACT

Brian Schoen

NDOT District 1

Highway Project Manager

302 Superior St.

Lincoln, NE 68521

brian.schoen@nebraska.gov

Phone 402-471-0850



US-34 North & South, Seward STP-15-2(117); C.N. 12080

CONSTRUCTION PHASING

