

# Bridge Design Manual



NEBRASKA

Good Life. Great Journey.

DEPARTMENT OF TRANSPORTATION  
BRIDGE DIVISION

February 23, 2026

This page intentionally left blank.

# Foreword

I am pleased to introduce you to the new Bridge Design Manual (BDM). If you are familiar with the Bridge Office Policy and Procedures (BOPP), you will first notice the name change. This updated title reflects the manual's true purpose—presenting policy and standards specifically related to bridge design within the department. While the BDM serves as a critical reference for bridge design policies, it is not intended to encompass all policies or procedures related to bridges in general. Our goal was to provide a clear, concise, and accessible resource for bridge design practices.

We greatly appreciate the patience of our community as we worked toward the publication of this comprehensive document. The development and maintenance of such a resource is no small feat, especially while meeting our ongoing obligations to the public. This delay does not reflect a lack of priority—it's quite the opposite. The manual is an essential tool, but its creation had to be balanced with the day-to-day demands of public service.

To ensure the most up-to-date information is always available, we are rolling out the manual chapter by chapter. This phased approach allows us to provide critical design guidance as it becomes ready while continuing to refine additional sections. Over the next year, more chapters will be released to keep the manual current with the evolving needs of our industry. In addition, interim revisions will be issued as NDOT Policy Letters, which will be posted on our website and take effect immediately upon transmittal. Please keep an eye out for these updates.

**Chapter 7** is a particularly exciting addition, as it focuses on Repair and Preservation. It is entirely new to the manual and represents a compilation of preferences and practices within the NDOT Bridge Division. We are eager to share this chapter with bridge owners across the state, believing it will serve as a valuable resource for aligning bridge repair and preservation practices statewide.

Recognizing the need for a structured approach to policy development, we established an executive BDM committee, along with subcommittees composed of members across the Bridge Division. This framework formalizes the process for creating, reviewing, and publishing bridge design policies and ensures active engagement from all levels within the division. By adopting a collaborative and systematic approach, we are able to incorporate national and regional research, ensuring our policies reflect the latest advancements and maintain NDOT's position at the forefront of bridge design.

This approach also supports the development of the next generation of bridge engineers. With the challenges our industry faces, it is more important than ever to equip younger and less experienced staff with the knowledge and resources they need to grow. This manual serves not only today's professionals but also as a guide for those just entering the field, ensuring they are well-prepared for the demands of modern bridge design.

I encourage everyone who uses this document to provide feedback and suggestions for revisions or future policy development. We've outlined the process for submitting suggestions to the Bridge Division, and I ask that we all actively engage in shaping what future policy could and should be. All input will be carefully considered, and revisions will be incorporated into the manual as appropriate.

I would like to extend a special thanks to Kyle Zillig for his vision and leadership in keeping the team organized and focused throughout the manual's development. Additionally, I want to thank Mike Vigil and Ben Ptacek for their efforts in developing the brand-new chapter on Repair and Preservation, and Matt Wieseler for his significant contributions to the development of the various chapters, and his dedication in formatting the manual. Lastly, a big thank you to Emilie Hudon, our newly appointed Bridge Policy and Quality Assurance Engineer, for her energy and leadership in driving us toward a final document in a remarkably short time. Your collective hard work and commitment have been invaluable throughout this evolution of the Bridge Design Manual.



Ross Barron, PE  
State Bridge Engineer

# Acknowledgments

The Bridge Division recognizes the efforts of the BDM Executive committee who helped to develop with the development of the 2024 BDM:

|                       |  |
|-----------------------|--|
| Emilie Hudon, PhD, PE | Bridge Policy and Quality Assurance Engineer           |
| Matt Wieseler, PE, SE | Bridge Policy and Quality Assurance Assistant Engineer |
| Kyle Zillig, PE       | Bridge Design Engineer                                 |
| Mike Vigil, PE        | Bridge Management Engineer                             |
| Kirk Harvey, PE       | Bridge Hydrology and Hydraulics Engineer               |
| Ross Barron, PE       | State Bridge Engineer                                  |

Additional assistance was provided by the consulting firm Benesch, and their representative, Aaron Buettner, PE.

## Revisions

The NDOT Bridge Design Manual provides current policies and procedures for use in structural design projects within Nebraska. To ensure that the manual remains up to date and appropriately reflects changes in NDOT's needs and requirements, its contents will be updated on a periodic basis.

Users of this manual should monitor the [Bridge Division website](#) for Policy Letters and revisions to the manual.

The Bridge Division is responsible for evaluating changes in structural engineering literature (e.g., updates to the AASHTO LRFD Specifications, issuance of new relevant publications, revisions to federal regulations) and for ensuring that these changes are appropriately addressed through revisions to the Bridge Design Manual. It is important that users of the manual inform NDOT of any inconsistencies, errors, need for clarification, or new ideas to support the goal of providing the best and most up-to-date information possible.

Our standard details can be found on ProjectWise. Please refer to these documents when making suggestions for drawing revisions.

Revisions to the Bridge Design Manual between major releases (interim revisions) are issued through Policy Letters. Requirements detailed in these memoranda are effective and enforceable on the effective date listed in the Letter and in the Transmittal Log located on the NDOT website.

To propose a revision to the Bridge Design Manual contact the Bridge Policy and Quality Assurance Engineer at [emilie.hudon@nebraska.gov](mailto:emilie.hudon@nebraska.gov), be sure to include "Bridge Design Manual" in the subject line and provide the following:

- Manual section number(s)
- Proposed revision
- Justification for revision

# Abbreviated Table of Contents

Chapter 1 – Introduction and Definitions  
Chapter 2 – Preliminary Design  
Chapter 3 – Loads and Load Factors  
Chapter 4 – Structural Analysis  
Chapter 5 – Concrete  
Chapter 6 – Steel Superstructures  
Chapter 7 – Repair and Preservation  
Chapter 8 – Deck Hydraulics  
Chapter 9 – Deck Design  
Chapter 10 – Foundations  
Chapter 11 – Substructures  
Chapter 12 – Box Culverts  
Chapter 13 – Railings  
Chapter 14 – Joints and Bearings  
Chapter 15 – Miscellaneous  
Appendix A – Special Provisions  
Appendix B – Base Sheets  
Appendix C – Plan Assembly & Drafting  
Appendix D – Miscellaneous Procedures

# Detailed Table of Contents

|  |       |
|--|-------|
| Foreword .....   | i     |
| Acknowledgments.....   | ii    |
| Revisions.....   | ii    |
| Abbreviated Table of Contents .....  | iii   |
| Detailed Table of Contents .....   | iv    |
| List of Figures.....   | xv    |
| List of Tables .....   | xviii |
| Chapter 1 – Introduction and Definitions.....                                  | 1-1   |
| 1.1–Introduction .....   | 1-1   |
| 1.2– Format.....   | 1-1   |
| 1.3–Publication and Maintenance .....  | 1-1   |
| 1.4–Purpose and Audience .....   | 1-1   |
| 1.5–Coordination with Other Documents.....                                     | 1-2   |
| 1.6–Current AASHTO specifications .....  | 1-2   |
| 1.7–Definitions.....   | 1-2   |
| 1.8–Quality assurance/quality control (QA/QC) process .....                    | 1-4   |
| 1.9–Operational importance of bridges.....                                     | 1-4   |
| 1.10–Abbreviations.....  | 1-4   |
| 1.11–References .....  | 1-6   |
| Chapter 3 – Loads and Load Factors .....                                       | 3-1   |
| 3.1–Introduction .....   | 3-1   |
| 3.2–Load Factors and Combinations.....   | 3-1   |
| 3.2.1–Strength Limit States .....  | 3-1   |
| 3.2.2–Extreme Event Load Combinations .....                                    | 3-1   |
| 3.3–Permanent Loads.....   | 3-1   |
| 3.3.1–Noncomposite Dead Loads (DC1) .....                                      | 3-1   |
| 3.3.2–Composite Dead Loads (DC2) .....   | 3-2   |
| 3.3.3–Future Surfacing and Utilities (DW).....                                 | 3-2   |
| 3.4–Live Loads.....  | 3-2   |
| 3.4.1–Pairs of Design Tandems.....   | 3-2   |
| 3.4.2–Live Load Deflection Limits for Steel and Concrete Superstructures ..... | 3-3   |
| 3.4.3–New, Reconstructed, and Rehabilitated Structures .....                   | 3-3   |
| 3.4.4–Existing Superstructures.....  | 3-3   |
| 3.4.5–Existing Substructures .....   | 3-3   |
| 3.4.6–Dynamic Load Allowance .....   | 3-3   |
| 3.4.7–Vehicular Collision Force.....   | 3-4   |
| 3.5–Water Loads .....  | 3-4   |
| 3.6–Wind Loads.....  | 3-4   |
| 3.7–Ice Loads.....   | 3-4   |
| 3.8–Earthquake Effects.....  | 3-4   |
| 3.9–Earth Pressure .....   | 3-5   |
| 3.10–Superimposed Deformations .....   | 3-5   |
| 3.10.1–Uniform Temperature .....   | 3-5   |
| 3.10.1.1–Movement Calculation .....  | 3-5   |
| 3.10.1.2–Force Effects Due to Temperature .....                                | 3-6   |
| 3.10.2–Shrinkage and Creep .....   | 3-6   |
| 3.11–Friction Forces.....  | 3-6   |
| 3.12–Vessel Collision .....  | 3-6   |
| 3.13–Blast Loading.....  | 3-6   |
| Chapter 5 – Concrete.....  | 5-1   |
| 5.1–Overview.....  | 5-1   |
| 5.2–Materials .....  | 5-1   |
| 5.2.1–Concrete .....   | 5-1   |
| 5.2.1.1–Strength of Concrete.....  | 5-1   |
| 5.2.1.1.1–CIP Concrete Superstructures .....                                   | 5-1   |
| 5.2.1.1.2–CIP Concrete Substructures .....                                     | 5-1   |
| 5.2.1.1.3–Prestressed Concrete Girders.....                                    | 5-2   |
| 5.2.1.1.4–CIP Concrete Box Culverts .....                                      | 5-2   |

|  |      |
|--|------|
| 5.2.1.1.5—Precast Concrete Box Culverts.....   | 5-2  |
| 5.2.1.2—Classes of Concrete.....   | 5-2  |
| 5.2.1.3—Unit Weight.....   | 5-2  |
| 5.2.1.4—Modulus of Elasticity.....   | 5-2  |
| 5.2.1.5—Shrinkage and Creep.....   | 5-3  |
| 5.2.1.6—Mass Concrete.....   | 5-3  |
| 5.2.1.7—Self-Consolidating Concrete.....   | 5-3  |
| 5.2.1.8—Ultra-High Performance Concrete.....   | 5-3  |
| 5.2.2—Mild Reinforcement.....  | 5-4  |
| 5.2.3—Prestressing Strands.....  | 5-4  |
| 5.3—Clear Cover.....   | 5-4  |
| 5.4—Cast-In-Place Concrete.....  | 5-5  |
| 5.4.1—General Information.....   | 5-5  |
| 5.4.2—Construction Joints.....   | 5-5  |
| 5.4.2.1—Mandatory Joints.....  | 5-6  |
| 5.4.2.2—Optional Joints.....   | 5-6  |
| 5.4.3—Concrete Slab Bridges.....   | 5-6  |
| 5.4.3.1—Slab Bridge Design Assumptions.....  | 5-7  |
| 5.4.3.2—Concrete Slab Base Sheet.....  | 5-7  |
| 5.4.3.3—Haunch Detail Over Intermediate Supports.....                                    | 5-11 |
| 5.4.3.3.1—Bridge Lengths of 60 ft. to 85 ft.....   | 5-11 |
| 5.4.3.3.2—Bridge Lengths of 90 ft. to 140 ft.....  | 5-11 |
| 5.5—Precast Prestressed Concrete Girders.....  | 5-11 |
| 5.5.1—General Information.....   | 5-11 |
| 5.5.1.1—Girder Templates.....  | 5-11 |
| 5.5.1.2—Composite Section Properties.....  | 5-11 |
| 5.5.1.3—Service III Load Combination.....  | 5-12 |
| 5.5.1.4—Strands.....   | 5-12 |
| 5.5.1.4.1—Extended Strands.....  | 5-12 |
| 5.5.1.4.2—Deflected Strands.....   | 5-12 |
| 5.5.1.4.3—Partially Debonded strands.....  | 5-13 |
| 5.5.1.4.4—Temporary Strands.....   | 5-13 |
| 5.5.1.5—Non-Prestressed Reinforcement.....   | 5-13 |
| 5.5.1.5.1—Transverse and End Zone Reinforcement.....                                     | 5-13 |
| 5.5.1.5.2—Negative Moment Reinforcing Steel in Bridge Deck at Intermediate Supports..... | 5-14 |
| 5.5.1.6—Vent Holes.....  | 5-14 |
| 5.5.1.7—Stay-in-Place Forms.....   | 5-15 |
| 5.5.1.8—Camber.....  | 5-15 |
| 5.5.1.9—Dead Load Deflections.....   | 5-15 |
| 5.5.2—Prestressed I-Girders.....   | 5-16 |
| 5.5.2.1—Section Properties and Layout.....   | 5-16 |
| 5.5.2.2—Strand Pattern.....  | 5-17 |
| 5.5.2.2.1—Cost-Optimized Strand Pattern.....   | 5-18 |
| 5.5.2.2.2—Limitations to Debonding.....  | 5-18 |
| 5.5.2.2.3—Limitations to Harping.....  | 5-18 |
| 5.5.2.3—Transverse Reinforcement.....  | 5-19 |
| 5.5.2.4—Intermediate Diaphragms.....   | 5-19 |
| 5.5.2.5—Vent Holes.....  | 5-19 |
| 5.5.3—Threaded Rod Connected I-Girders.....  | 5-19 |
| 5.5.4—Prestressed Inverted Tee Girders.....  | 5-20 |
| 5.5.4.1—Section Properties and Layout.....   | 5-20 |
| 5.5.4.2—Strand Pattern.....  | 5-21 |
| 5.5.4.3—Transverse Reinforcement.....  | 5-21 |
| 5.5.4.4—Intermediate Diaphragms.....   | 5-22 |
| 5.5.4.5—Vent Holes.....  | 5-23 |
| 5.5.4.6—Live Load Distribution.....  | 5-23 |
| 5.6—Other Precast elements.....  | 5-23 |
| 5.6.1—Non-Prestressed Elements.....  | 5-23 |
| 5.6.2—Prestressed Deck Panels.....   | 5-24 |
| 5.6.3—Post Tensioned Elements.....   | 5-24 |
| 5.6.3.1—Post Tensioned I-Girders.....  | 5-24 |
| 5.6.4—UHPC Decked I-Girders.....   | 5-24 |
| 5.7—References.....  | 5-24 |

Chapter 6 – Steel Superstructures ..... 6-1

- 6.1—Overview ..... 6-1
- 6.2—Materials ..... 6-1
  - 6.2.1—Grades ..... 6-1
  - 6.2.2—Uses ..... 6-1
  - 6.2.3—Painting of Weathering Steel ..... 6-2
    - 6.2.3.1—Zone Painting ..... 6-2
    - 6.2.3.2—Full Painting ..... 6-3
  - 6.2.4—Fracture Toughness Requirements ..... 6-4
  - 6.2.5—Bolts, Nuts and Washers ..... 6-5
  - 6.2.6—Welds ..... 6-5
- 6.3—Girder Erection Plans ..... 6-5
- 6.4—Connections ..... 6-6
  - 6.4.1—Welded Connections ..... 6-6
  - 6.4.2—Bolted Connections ..... 6-6
  - 6.4.3—Field Splices ..... 6-6
- 6.5—Composite Design and Shear Connectors ..... 6-7
  - 6.5.1—Composite Girder Design ..... 6-7
  - 6.5.2—Shear Connectors ..... 6-7
- 6.6—I-Section Flexural Members ..... 6-7
  - 6.6.1—General Design Considerations ..... 6-7
  - 6.6.2—Stiffeners ..... 6-8
    - 6.6.2.1—Bearing Stiffeners ..... 6-8
    - 6.6.2.2—Intermediate Connection Plate Stiffeners ..... 6-8
    - 6.6.2.3—Intermediate Stiffeners ..... 6-8
      - 6.6.2.3.1—Straight Girders ..... 6-9
      - 6.6.2.3.2—Horizontally Curved Girders ..... 6-9
  - 6.6.3—Drip plates ..... 6-9
  - 6.6.4—Rolled Beam Girders ..... 6-9
    - 6.6.4.1—General Design Considerations ..... 6-9
    - 6.6.4.2—Camber and Blocking ..... 6-10
    - 6.6.4.3—Shims ..... 6-11
    - 6.6.4.4—Field Splice Elimination ..... 6-11
  - 6.6.5—Welded Plate Girders ..... 6-12
    - 6.6.5.1—General Design Considerations ..... 6-12
    - 6.6.5.2—Field Sections ..... 6-12
    - 6.6.5.3—Special Considerations for Horizontally Curved Girders ..... 6-12
    - 6.6.5.4—Flange Plates ..... 6-13
    - 6.6.5.5—Web Plates ..... 6-14
    - 6.6.5.6—Hybrid Girders ..... 6-15
    - 6.6.5.7—Girder Fit Condition ..... 6-15
    - 6.6.5.8—Camber and Blocking ..... 6-15
    - 6.6.5.9—Shims ..... 6-17
  - 6.6.6—Cross-frames and Diaphragms ..... 6-17
    - 6.6.6.1—General Design Considerations ..... 6-17
    - 6.6.6.2—Cross-frames ..... 6-18
      - 6.6.6.2.1—Standard Cross-frame ..... 6-19
    - 6.6.6.3—Diaphragms ..... 6-20
- 6.7—Box and Tub Girders ..... 6-20
- 6.8—Fabrication Reviews ..... 6-20
- 6.9—References ..... 6-20
- 6.10—Referenced Cells ..... 6-21

Chapter 7 – Repair and Preservation ..... 7-1

- 7.1—Overview ..... 7-1
  - 7.1.1—Scoping of Repair and Preservation Projects ..... 7-1
  - 7.1.2—Organization of this Chapter ..... 7-1
- 7.2—Superstructure Preservation with Overlays ..... 7-2
  - 7.2.1—Thin Overlays ..... 7-2
    - 7.2.1.1—Epoxy Polymer Overlay ..... 7-2
    - 7.2.1.2—Deck Surface Treatment ..... 7-2
  - 7.2.2—Rigid Overlays ..... 7-2
    - 7.2.2.1—Polyester Polymer Concrete Overlay ..... 7-2

|   |      |
|---|------|
| 7.2.2.2—47B-OL Concrete Overlay .....   | 7-2  |
| 7.2.3—Asphalt Overlay and Waterproof Membranes.....                                   | 7-3  |
| 7.2.3.1—Asphalt Overlay Details.....  | 7-3  |
| 7.2.3.1.1—Mix and Placement of Overlay.....   | 7-3  |
| 7.2.3.1.2—Thickness of Overlay .....  | 7-3  |
| 7.2.3.1.3— Wick Drains.....   | 7-4  |
| 7.2.3.1.4—Payment.....  | 7-4  |
| 7.2.3.2—Waterproof Membrane Details.....  | 7-5  |
| 7.2.3.2.1—Special Provisions and Tapes.....   | 7-6  |
| 7.2.3.2.2—Preformed Fabric Membranes .....  | 7-6  |
| 7.2.3.2.3—Liquid-Applied Membranes .....  | 7-6  |
| 7.2.3.2.3a—Cold Liquid-Applied Membrane .....   | 7-6  |
| 7.2.3.2.3b—Hot Liquid-Applied Membrane .....  | 7-6  |
| 7.2.3.2.4—Payment.....  | 7-7  |
| 7.2.3.3—Curbs on Open Rails.....  | 7-7  |
| 7.2.3.4—Expansion Joint Selection with Asphalt Overlay Projects.....                  | 7-7  |
| 7.2.3.4.1—Bridge Joint Nosing with Asphalt Overlays.....                              | 7-9  |
| 7.2.3.4.2—Asphalt Plug Joints.....  | 7-10 |
| 7.2.3.4.3—Asphalt Overlay Saw & Seal Joints .....                                     | 7-10 |
| 7.2.3.4.3a—End of Floor—Non-Movement.....   | 7-11 |
| 7.2.3.4.3b—Grade Beams or Sleeper Slabs .....   | 7-11 |
| 7.2.3.4.3c—End of Paving Pressure Relief Joint.....                                   | 7-12 |
| 7.2.3.5—Delayed preservation of New Decks with AC+M .....                             | 7-14 |
| 7.2.3.6—Removal of Existing Overlays.....   | 7-14 |
| 7.2.3.6.1—Concrete Overlay to be removed.....   | 7-14 |
| 7.2.3.6.1a—Parabolic deck cross-section .....   | 7-15 |
| 7.2.3.6.2—Asphalt Overlay to be removed.....  | 7-15 |
| 7.2.3.6.3—Waterproof Membrane to be removed .....                                     | 7-15 |
| 7.3—Common Remodeling Guidelines and Examples .....                                   | 7-15 |
| 7.3.1—Approach Slab Addition or Replacement.....                                      | 7-15 |
| 7.3.1.1—Approach Slab .....   | 7-15 |
| 7.3.1.1.1—General .....   | 7-15 |
| 7.3.1.1.2—Preliminary Investigation .....   | 7-16 |
| 7.3.1.1.3—Abutment Pile Evaluation .....  | 7-16 |
| 7.3.1.1.4—Use of Relative Elevations .....  | 7-16 |
| 7.3.1.2—Existing Wingwall Remodel.....  | 7-17 |
| 7.3.1.3—Adding or Replacing Sheet Pile at Abutments .....                             | 7-18 |
| 7.3.1.4—Turndown Modifications .....  | 7-18 |
| 7.3.1.4.1—Preliminary Investigation.....  | 7-18 |
| 7.3.1.4.2—Existing Abutment/Backwall Considerations .....                             | 7-18 |
| 7.3.1.4.2a—Backwall Abutment .....  | 7-19 |
| 7.3.1.4.2b—Bearings with Anchor Rods.....   | 7-20 |
| 7.3.1.4.2c—Existing Abutment Cap without Pedestals & Heavy Skew .....                 | 7-21 |
| 7.3.1.5—Adding Turndowns.....   | 7-21 |
| 7.3.1.5.1—Full Depth Turndown .....   | 7-21 |
| 7.3.1.5.2—Partial Turndown .....  | 7-22 |
| 7.3.1.6—Approach Seat Modifications.....  | 7-23 |
| 7.3.1.7— Grade Beam .....   | 7-23 |
| 7.3.1.7.1—Geotechnical Coordination.....  | 7-23 |
| 7.3.1.7.2—Piling.....   | 7-24 |
| 7.3.1.7.3—Field Measured Cut-off Elevations.....                                      | 7-24 |
| 7.3.1.8—Granular Backfill .....   | 7-25 |
| 7.3.1.8.1—Existing Granular Backfill .....  | 7-25 |
| 7.3.1.8.2—Drainage of Granular Backfill .....   | 7-25 |
| 7.3.2—Rail or Buttress Remodel .....  | 7-28 |
| 7.3.2.1—Buttress Updates .....  | 7-28 |
| 7.3.2.1.1—New Approach Slab .....   | 7-28 |
| 7.3.2.1.2—Existing Approaches with an Existing End Section on the Paving Section..... | 7-29 |
| 7.3.2.1.3—Buttress Mounted on Wings or on End of Bridge at End of Floor.....          | 7-29 |
| 7.3.2.1.3a—Collision Damage.....  | 7-29 |
| 7.3.2.1.4—Flared Wings .....  | 7-30 |
| 7.3.3—Bridge Joints Remodel—Repair or Replacement .....                               | 7-30 |
| 7.3.3.1—Elimination of Deck Joints .....  | 7-30 |

|  |      |
|--|------|
| 7.3.3.2—Expansion Joint Remodeling.....                              | 7-30 |
| 7.3.3.2.1—Expansion Joint at Intermediate Supports .....             | 7-31 |
| 7.3.3.2.2—Expansion Joint at EOF.....                                | 7-32 |
| 7.3.3.2.3—Expansion Joint at Grade Beam or Sleeper Slab .....        | 7-33 |
| 7.3.4—Bearing Replacement .....                                      | 7-34 |
| 7.3.4.1—Pedestal Retrofit.....                                       | 7-34 |
| 7.3.4.2—Anchorage Considerations.....                                | 7-36 |
| 7.3.4.3—Temporary Support for Bearing Replacement .....              | 7-36 |
| 7.4—Common Repair Guidelines and Examples.....                       | 7-36 |
| 7.4.1—Bridge Deck and Approach Slab Repair .....                     | 7-36 |
| 7.4.1.1—Concrete Repairs .....                                       | 7-36 |
| 7.4.1.2—Crack Repairs with Cross Stitching .....                     | 7-37 |
| 7.4.2—Concrete Patching.....   | 7-39 |
| 7.4.2.1—Overview .....   | 7-39 |
| 7.4.2.1.1—Typical Locations .....                                    | 7-39 |
| 7.4.2.2—Plan Considerations .....                                    | 7-41 |
| 7.4.2.2.1—General .....  | 7-41 |
| 7.4.2.2.2—Quantity Estimates.....                                    | 7-42 |
| 7.4.2.3—Material Considerations .....                                | 7-42 |
| 7.4.2.3.1—Option to Require Shotcrete for Patching .....             | 7-42 |
| 7.4.3—Crack Epoxy Injection .....                                    | 7-43 |
| 7.4.4—Girder Repairs.....  | 7-44 |
| 7.4.4.1—Steel Girder Repairs.....                                    | 7-44 |
| 7.4.4.1.1—Pin and Hanger Repair .....                                | 7-44 |
| 7.4.4.1.2—Fatigue Retrofit/Crack Repair .....                        | 7-45 |
| 7.4.4.1.3—Heat Straightening of Steel Girders (Impact) .....         | 7-45 |
| 7.4.4.2—Prestressed Concrete Girder Repairs.....                     | 7-48 |
| 7.4.4.2.1—Crack Epoxy Injection .....                                | 7-48 |
| 7.4.4.2.2—Concrete Repair (Deterioration).....                       | 7-48 |
| 7.4.4.2.3—Impact Repair.....   | 7-49 |
| 7.4.4.2.3a—Concrete Repair (Impact).....                             | 7-49 |
| 7.4.4.2.3b—Strand Repair (Impact).....                               | 7-49 |
| 7.4.4.2.4—UHPC Repairs .....   | 7-51 |
| 7.4.5—Steel Pile Repair and Preservation .....                       | 7-51 |
| 7.4.5.1—Concrete Encasement .....                                    | 7-51 |
| 7.4.5.2—FRP Encasement .....   | 7-51 |
| 7.4.6—Resetting Rocker Bearings .....                                | 7-51 |
| 7.4.7—Floor Drain Retrofits.....                                     | 7-53 |
| 7.4.7.1—Drains in Closed Rails .....                                 | 7-53 |
| 7.4.7.2—Drains in Shoulders.....                                     | 7-54 |
| 7.5—Steel Painting Guidelines and Examples .....                     | 7-56 |
| 7.5.1—Zone Painting of Girder Ends .....                             | 7-56 |
| 7.5.2—Painting Existing Bearings .....                               | 7-56 |
| 7.5.3—Painting Piles.....  | 7-57 |
| 7.6—Special Considerations for Historic Bridges .....                | 7-57 |
| 7.6.1—Priorities for Treatment of Historic Bridges.....              | 7-57 |
| 7.6.2—Alternative Evaluation and Documentation – A Requirement ..... | 7-57 |
| 7.6.3—Maintenance Activities on Historical Bridges .....             | 7-58 |
| 7.7—References.....  | 7-59 |
| Chapter 8 – Deck Hydraulics .....                                    | 8-1  |
| 8.1—Deck Hydraulics .....  | 8-1  |
| 8.2—Rail Policy.....   | 8-1  |
| 8.3—Drainage through Open Rails .....                                | 8-1  |
| 8.4—Drainage through Closed Rail .....                               | 8-1  |
| 8.4.1—Without Deck Drains .....                                      | 8-1  |
| 8.4.2—With Deck Drains .....   | 8-1  |
| 8.5—Analysis and Design.....   | 8-2  |
| 8.6—Location Guidelines .....  | 8-2  |
| 8.7—Deck Drain Runoff .....  | 8-2  |
| 8.7.1—Free Fall .....  | 8-2  |
| 8.7.2—Drainage Systems .....   | 8-3  |
| 8.8—References.....  | 8-3  |

|  |      |
|--|------|
| Chapter 9 – Deck Design.....   | 9-1  |
| 9.1—General Deck Criteria.....   | 9-1  |
| 9.2—Cast-in-Place Decks.....   | 9-1  |
| 9.2.1—Deck Thickness for New Construction and Redecks.....             | 9-1  |
| 9.2.2—Reinforcement Details.....                                       | 9-2  |
| 9.2.2.1—Transverse Bars.....   | 9-2  |
| 9.2.2.2—Longitudinal Bars.....   | 9-3  |
| 9.2.2.3—Skewed Decks.....  | 9-3  |
| 9.2.3—Cantilever Design.....   | 9-3  |
| 9.2.4—IT Girder Decks.....   | 9-4  |
| 9.2.4.1—Interstate and Heavy Barriers.....                             | 9-4  |
| 9.2.4.2—Other Structures.....  | 9-4  |
| 9.2.5—Construction Joints and Pour Sequencing.....                     | 9-5  |
| 9.2.5.1—Continuous Placement Sequence.....                             | 9-5  |
| 9.2.5.2—Skip Placement Sequence.....                                   | 9-5  |
| 9.2.5.3—Pouring Diagram Calculations.....                              | 9-6  |
| 9.2.6—Drip Bead Detail.....  | 9-7  |
| 9.2.7—Roadway Crown.....   | 9-7  |
| 9.2.8—Deck Surface Finish.....   | 9-8  |
| 9.2.9—Phased Decks.....  | 9-8  |
| 9.2.10—Stay in Place Forms.....  | 9-9  |
| 9.2.11—Widening.....   | 9-10 |
| 9.3—NU Deck.....   | 9-10 |
| 9.4—Composite Action on Concrete Girders.....                          | 9-10 |
| 9.4.1—Design Assumptions.....  | 9-10 |
| 9.4.2—Reinforcement Development.....                                   | 9-10 |
| 9.5—Turndowns and Diaphragms.....                                      | 9-11 |
| 9.5.1—Blockouts for Anchor Rods.....                                   | 9-12 |
| 9.5.2—Slab Turndown at Abutments.....                                  | 9-12 |
| 9.5.3—Diaphragm at Intermediate Supports.....                          | 9-15 |
| 9.6—References.....  | 9-16 |
| 9.7—Referenced Cells.....  | 9-17 |
| Chapter 10 – Foundations.....  | 10-1 |
| 10.1—Overview.....   | 10-1 |
| 10.1.1—Design Responsibility.....                                      | 10-1 |
| 10.1.2—Coordination with the Geotechnical Engineer.....                | 10-1 |
| 10.1.3—Downdrag Effects.....   | 10-2 |
| 10.2—Driven Piles.....   | 10-2 |
| 10.2.1—Maximum Spacing.....  | 10-2 |
| 10.2.2—Minimum Spacing.....  | 10-2 |
| 10.2.3—Battered Piles.....   | 10-2 |
| 10.2.4—Horizontal Pile Load for Preliminary Design.....                | 10-2 |
| 10.2.5—Ground Vibration when Driving Close to Adjacent Structures..... | 10-3 |
| 10.2.6—Minimum penetration.....  | 10-4 |
| 10.2.7—Pile Cut-Off Elevations.....                                    | 10-4 |
| 10.2.8—Test piles.....   | 10-4 |
| 10.2.9—Steel Piles.....  | 10-4 |
| 10.2.9.1—Corrosive soils.....  | 10-4 |
| 10.2.9.2—H-Piles.....  | 10-4 |
| 10.2.9.3—Steel Pipe Piles.....   | 10-4 |
| 10.2.9.4—Splice Details.....   | 10-5 |
| 10.2.9.5—Uplift Details.....   | 10-5 |
| 10.2.10—Precast/Prestressed Concrete Piles.....                        | 10-5 |
| 10.3—Drilled Shafts.....   | 10-6 |
| 10.3.1—Analysis and Design.....  | 10-6 |
| 10.3.2—Dimensions.....   | 10-6 |
| 10.3.3—Details.....  | 10-7 |
| 10.3.4—Reinforcement Details.....                                      | 10-7 |
| 10.3.5—Plan Details.....   | 10-8 |
| 10.3.6—Test Shaft.....   | 10-8 |
| 10.3.7—Special Provision.....  | 10-8 |
| 10.4—Helical Piles.....  | 10-9 |

|  |       |
|--|-------|
| 10.4.1—Use .....   | 10-9  |
| 10.4.2—Minimum Spacing .....                                   | 10-9  |
| 10.4.3—Maximum capacity .....                                  | 10-9  |
| 10.4.4—Special Provision .....                                 | 10-9  |
| 10.5—Micropiles .....  | 10-9  |
| 10.5.1—Use .....   | 10-9  |
| 10.6—Spread Footings .....                                     | 10-10 |
| 10.7—References .....  | 10-10 |
| Chapter 13 — Railings .....                                    | 13-1  |
| 13.1—Overview .....  | 13-1  |
| 13.1.1—Design Criteria .....                                   | 13-1  |
| 13.1.1.1—New Construction .....                                | 13-1  |
| 13.1.1.1.1—Rail Type .....                                     | 13-1  |
| 13.1.1.1.2—Rail Height .....                                   | 13-1  |
| 13.1.1.2—Existing Bridges .....                                | 13-2  |
| 13.1.2—Closed Rail Requirements .....                          | 13-2  |
| 13.1.3—Embankment Protection for Open Rails .....              | 13-2  |
| 13.1.4—General .....   | 13-2  |
| 13.2—39 in. Rails .....  | 13-3  |
| 13.2.1—Single Slope Closed Rail .....                          | 13-3  |
| 13.2.2—Open Concrete Rail .....                                | 13-3  |
| 13.2.3—Buttress Details .....                                  | 13-4  |
| 13.3—NU Rails .....  | 13-5  |
| 13.3.1—NU Open Concrete Rail .....                             | 13-5  |
| 13.3.2—Buttress Details .....                                  | 13-6  |
| 13.4—Legacy Rails .....  | 13-6  |
| 13.4.1—Overview .....  | 13-6  |
| 13.4.2—29 in. Nebraska Rail .....                              | 13-6  |
| 13.4.3—Concrete Barrier .....                                  | 13-7  |
| 13.4.4—Thrie Beam Guardrail Connections for Legacy Rails ..... | 13-9  |
| 13.4.4.1—Use of Standard End Sections (NCHRP 350) .....        | 13-9  |
| 13.4.4.2—Thrie-Beam Guardrail Connections .....                | 13-9  |
| 13.5—Pedestrian Barrier Rails .....                            | 13-10 |
| 13.6—Fence .....   | 13-11 |
| 13.6.1—Pedestrian Fence .....                                  | 13-11 |
| 13.6.2—Railroad Protection Fence .....                         | 13-11 |
| 13.6.3—Fence Layout .....                                      | 13-11 |
| 13.6.4—Expansion Joints .....                                  | 13-11 |
| 13.6.5—Base Sheets .....                                       | 13-12 |
| 13.7—References .....  | 13-12 |
| 13.8—Referenced Cells .....                                    | 13-13 |
| Appendix C — Plan Assembly & Drafting .....                    | C-1   |
| C.1—General Plan Info .....                                    | C-1   |
| C.2—Title Blocks .....   | C-1   |
| C.3—Plan Sheet Requirements .....                              | C-1   |
| C.4—Plan Revisions .....                                       | C-1   |
| C.5—Standard Notes .....                                       | C-1   |
| C.5.1—Front Sheet Notes .....                                  | C-1   |
| C.5.1.1—General .....  | C-1   |
| C.5.1.2—Excavation .....                                       | C-2   |
| C.5.1.3—Substructure .....                                     | C-2   |
| C.5.1.4—Concrete & Reinforcement .....                         | C-2   |
| C.5.1.5—Prestressed Girders .....                              | C-2   |
| C.5.1.6—Steel Girders .....                                    | C-3   |
| C.5.1.7—Miscellaneous .....                                    | C-4   |
| C.5.1.8—Repair/Rehab .....                                     | C-4   |
| C.5.1.9—Utilities .....  | C-4   |
| C.5.2—Geology Sheet Notes .....                                | C-5   |
| C.5.2.1—General .....  | C-5   |
| C.5.2.2—Borings .....  | C-5   |
| C.5.2.3—Bearing Piles .....                                    | C-5   |
| C.5.2.4—Test Piles .....                                       | C-5   |

Front Matter

---

|                                 |     |
|---------------------------------|-----|
| C.5.2.5—MSE Wall Piling .....   | C-6 |
| C.5.2.6—Integral Abutments..... | C-6 |
| C.6—Pay Items.....              | C-6 |
| C.7—Plan Sheet Scaling.....     | C-6 |

This page intentionally left blank.

# List of Figures

Figure 3.1—Buoyant Force Cross Section ..... 3-4

Figure 5.1—Slab Construction Joint for Slab Thickness  $\leq$  8.5 in. .... 5-5

Figure 5.2—Slab Construction Joint for Slab Thickness  $>$  8.5 in. .... 5-5

Figure 5.3—Precast Girder Vent Hole Location ..... 5-14

Figure 5.4—NU Girder Dimensions..... 5-16

Figure 5.5—NU Girder Strand Pattern..... 5-18

Figure 5.6—IT Girder Dimensions..... 5-20

Figure 5.7—IT Girder Strand Pattern ..... 5-21

Figure 5.8—Location of intermediate diaphragm for phased construction of IT girder bridge..... 5-22

Figure 5.9—IT Girder Intermediate Concrete Diaphragm..... 5-23

Figure 6.1—Exterior Girder Zone Coat Detail..... 6-2

Figure 6.2—Top Flange Paint Detail ..... 6-2

Figure 6.3—Girder End Zone Coat Detail..... 6-3

Figure 6.4—Rolled Beam Girder Blocking Diagram..... 6-10

Figure 6.5—Welded Plate Girder Camber and Blocking Diagram..... 6-16

Figure 6.6—Cross-frame Welding..... 6-18

Figure 6.7—Standard Cross-frame Detail ..... 6-19

Figure 6.8—CHARP1 Cell (Steel Girder Library) ..... 6-21

Figure 6.10—CHARP2 Cell (Steel Girder Library)..... 6-21

Figure 6.9—SHIM WP Cell (Bridge Deck Library)..... 6-21

Figure 6.11—SHIM RB Cell (Bridge Deck Library)..... 6-21

Figure 7.1—Tapered Asphalt Overlay ..... 7-4

Figure 7.2—Membrane Selection Flowchart ..... 7-5

Figure 7.3—Asphalt Plug Joint Standard Detail..... 7-10

Figure 7.4— Saw and Seal Joint at EOF (Non-Movement) ..... 7-11

Figure 7.5—Saw and Seal Joint at Grade Beam (Expansion Joint) ..... 7-11

Figure 7.6—Saw and Seal Joint at EOP (Non-Movement)..... 7-12

Figure 7.7—Saw and Seal Joint at EOP (Existing 1 in. Joint) ..... 7-12

Figure 7.8—Saw and Seal Joint at EOP (Existing 3 in. Joint) ..... 7-13

Figure 7.9— Removal and Asphalt Overlay Detail for Bridges with Existing Concrete Overlays ..... 7-14

Figure 7.10—Milling of Existing Concrete Overlay for Parabolic Bridge Decks ..... 7-15

Figure 7.11—Base Layout for Use of Relative Elevations in Approach Slab Remodel ..... 7-17

Figure 7.12—Partial Wingwall Removal to Accommodate New Approach Slab ..... 7-17

Figure 7.13— Remodeling of Abutment with Backwall to Semi-Integral Abutment with Expansion Joint at Grade Beam. Bearings without Anchor Rods ..... 7-19

Figure 7.14—Remodeling of Abutment with Backwall to Semi-Integral Abutment with Expansion Joint at Grade Beam. Bearings with Anchor Rods ..... 7-20

Figure 7.16—Joint Filler for Turndown Remodel ..... 7-21

Figure 7.15— Stepped Grade Beam to Guide Expansion for High Skews without Pedestals at Abutments ..... 7-21

Figure 7.17—Partial Turndown with HDPE Sliding Plates ..... 7-22

Figure 7.18— Reuse of Existing Borings for New Approach Slab ..... 7-24

Figure 7.19—Section of Granular Backfill showing Extents of Existing Backfill ..... 7-25

Figure 7.20—Abutment Drainage Detail with New Approach Slab Seat ..... 7-26

Figure 7.21—Abutment Drainage Details with Drainage Daylighting ..... 7-27

Figure 7.22—Deck Joint Repair at Pier..... 7-31

Figure 7.23—Joint Remodel at EOF with Backwall ..... 7-32

Figure 7.24—Expansion Joint Remodel, Pressure Relief Joint over Grade Beam or Sleeper Slab ..... 7-33

Figure 7.25—Pedestal Retrofit for Bearing Replacement ..... 7-35

Figure 7.26—Cross Stitching Approach Repair Detail ..... 7-37

Figure 7.27—Level of Cracking Appropriate for Cross-Stitch Repair as shown in [Figure 7.26](#)..... 7-38

Figure 7.28—Concrete Patching at Abutment with Shotcrete..... 7-40

Figure 7.29—Concrete Patching at Deck Edges, with Shotcrete..... 7-40

Figure 7.30—Concrete Patching at Bridge Rail, with Shotcrete..... 7-40

Figure 7.31—Concrete Patching as Shown on Plans with Hatching ..... 7-41

Figure 7.32—Concrete Patching Callout on General Plan ..... 7-41

Figure 7.33—Note on Plan for Requiring Use of Shotcrete ..... 7-43

Figure 7.34—Epoxy Crack Injection Plan Note ..... 7-43

Figure 7.35—Epoxy Crack Injection (Before on the Left, and After on the Right) ..... 7-44

Figure 7.36—Crack Arresting Bushings on S012 00398 ..... 7-45

Figure 7.37—Girder after Heat Straightening on S129 00039 ..... 7-46

Figure 7.38—Crack Epoxy Injection on S070 10755 ..... 7-48

Figure 7.39—Crack Epoxy Injection on S002 50816 ..... 7-48

Figure 7.40—Strand Repair Method after Impact ..... 7-50

Figure 7.41—Rocker Bearing Reset and Lubrication ..... 7-52

Figure 7.42—Retrofit for Drain in Closed Rails ..... 7-53

Figure 7.43—Shoulder Drain with Frame on S480 00310B ..... 7-54

Figure 7.44—Drain in Driving Lane ..... 7-54

Figure 7.45—Frame Detail Around Shoulder Drain for Overlays ..... 7-55

Figure 7.46—Painting Existing Bearing ..... 7-56

Figure 9.1—Effective Length and Design Depth ..... 9-2

Figure 9.2—Cantilever Length and Reinforcement Section..... 9-4

Figure 9.3—Example Pouring Diagram..... 9-7

Figure 9.4—Differential Deflection Cross Section (for illustrative purposes)..... 9-9

Figure 9.5—Preferred Hat Bar Detail..... 9-11

Figure 9.6—Anchor Rod Blockouts..... 9-12

Figure 9.7—IT Girder Slab Turndown (Required on IT 300, Optional on IT 400)..... 9-13

Figure 9.8—IT Girder Slab Turndown (Required on IT 500 and Deeper, Optional on IT 400) ..... 9-13

Figure 9.9—I Shaped Girder Slab Turndown (Concrete or Steel)..... 9-14

Figure 9.10—IT Girder Diaphragm ..... 9-15

Figure 9.11—I Shaped Girder Diaphragm (Concrete or Steel) ..... 9-16

Figure 9.13—POURSQ Cell (Bridge Deck Library)..... 9-17

Figure 9.12—SHIM SHOT IT Cell (Bridge Deck Library)..... 9-17

Figure 9.14—DRIPBnew Cell (Bridge Deck Library)..... 9-18

Figure 9.16—CROWN Cell (Bridge Deck Library) ..... 9-18

Figure 9.17—Ext. Strand Splay Cell (NU Details Library) ..... 9-18

Figure 9.15—DRIPB Cell (Bridge Deck Library) ..... 9-18

Figure 10.1—Steel Pile Uplift Details..... 10-5

Figure 13.1—39 in. SSCR Bridge Rail Reinforcing ..... 13-3

Figure 13.2—39 in. OCR Bridge Rail Reinforcing ..... 13-4

Figure 13.3—39 in. Rail Buttress — Thrie Beam Terminal Layout ..... 13-4

Figure 13.4—NU Bridge Rail Reinforcing (shown here for 42 in. rail, see Base Sheets for 34 in. rail)..... 13-5

Figure 13.5—NU Bridge Rail Buttress — Thrie Beam Terminal Layout..... 13-6

Figure 13.6—29 in. Nebraska Rail Reinforcing Sections ..... 13-7

Figure 13.7—Concrete Barrier Reinforcing Sections ..... 13-8

Figure 13.8—Plan View of Standard Legacy Rail End Sections (NCHRP 350) ..... 13-9

Figure 13.9—Legacy Rails — Guardrail End Section Dimensions..... 13-10

Figure 13.10—Legacy Rails — Thrie Beam Terminal Layout ..... 13-10

Figure 13.11—39 in. SSCR Sidewalk Clear Width..... 13-12

Figure 13.12— Rail Sec 39 SSCL Cell (Barriers and Rails Library) ..... 13-13

Figure 13.15—Rail Sec 42 NUMD Cell (Barriers and Rails Library) ..... 13-13

Figure 13.18—Rail Sec 34 NUCL Alt Cell (Barriers and Rails Library)..... 13-13

Figure 13.13—Rail Sec 39 OCBR Cell (Barriers and Rails Library) ..... 13-13

Figure 13.16—Rail Sec 42 NUOP Cell (Barriers and Rails Library) ..... 13-13

Figure 13.19—Rail Sec 34 NUOP Cell (Barriers and Rails Library) ..... 13-13

Figure 13.14—Rail Sec 42 NUCL Cell (Barriers and Rails Library)..... 13-13

Figure 13.17—Rail Sec 34 NUCL Cell (Barriers and Rails Library)..... 13-13

Figure 13.20—Rail Sec 34 NUOP Alt Cell (Barriers and Rails Library) ..... 13-13

Figure 13.21—WP Barrier Sec Cell (Barriers and Rails Library) ..... 13-14

Figure 13.24—Ex Barrier Sec 42 NJ Cell (Barriers and Rails Library) ..... 13-14

Figure 13.27—Ex Rail Sec 29 NEBOP Cell (Barriers and Rails Library) ..... 13-14

Figure 13.22—Temp Barrier Sec Cell (Barriers and Rails Library) ..... 13-14

Figure 13.25—Ex Barrier Sec 42 NJMD Cell (Barriers and Rails Library) ..... 13-14

Figure 13.28—Ex Curb Sec 10.5 Cell (Barriers and Rails Library) ..... 13-14

Figure 13.30—Ex Rail Sec 1755C Cell (Barriers and Rails Library) ..... 13-14

Figure 13.23—Ex Barrier Sec 32 NJ Cell (Barriers and Rails Library) ..... 13-14

Figure 13.26—Ex Rail Sec 29 NEBCL Cell (Barriers and Rails Library) ..... 13-14

Figure 13.29—Ex Curb Sec 20 Cell (Barriers and Rails Library) ..... 13-14

Figure 13.31—Ex Rail Sec 1753C Cell (Barriers and Rails Library) ..... 13-14

# List of Tables

Table 3.1—Rail Dead Loads ..... 3-2

Table 3.2—Uniform Temperature Parameters ..... 3-5

Table 5.1—Standard Concrete Classes and Compressive Strengths ..... 5-1

Table 5.2—CSB Dimensions ..... 5-8

Table 5.3—CSB Reactions at Abutments and Intermediate Supports ..... 5-9

Table 5.4—CSB Reinforcement ..... 5-10

Table 5.5—4 ft. Haunch Bill of Bars ..... 5-11

Table 5.6—6 ft. Haunch Bill of Bars ..... 5-11

Table 5.7—NU Girder Section Properties ..... 5-16

Table 5.8—IT Girder Section Properties ..... 5-20

Table 6.1—Welding Electrode Compatibility ..... 6-5

Table 6.2—Preliminary Cross-frame or Diaphragm Spacing for Curved Girders ..... 6-13

Table 6.3—Welded Plate Girder Fit Conditions ..... 6-15

Table 7.1—Selection Guide for Joints Located Over Grade Beams on Existing Approaches for Placement of Asphalt Overlay ..... 7-8

Table 7.2—Selection Guide for Joints Located Over Grade Beams on New Approach Slabs with Asphalt Overlay ..... 7-8

Table 7.3—Selection Guide for Joints on Deck or at End of Floor on Asphalt Overlay Projects ..... 7-9

Table 7.4—Examples of Buttress Update with New Approaches ..... 7-28

Table 7.5—Examples of Buttress Updates with Existing Approach Slabs and without At-Grade EJ Blockout ..... 7-29

Table 7.6—Examples of Buttress Updates with Existing Approach Slab and At-Grade EJ Blockout ..... 7-29

Table 7.7—Examples of Buttress Updates With Existing Approach Slabs and with Existing Buttress Mounted to Deck or Wings ..... 7-29

Table 7.8—Examples for Buttress Updates without Approach Slabs and with Flared Wings ..... 7-30

Table 7.9—Guidance For Expansion Joint Remodeling ..... 7-30

Table 7.10—Deck Repair Area based on Condition ..... 7-36

Table 7.11—Pin and Hanger Repair Examples ..... 7-44

Table 7.12—Steel Crack Repair Example ..... 7-45

Table 7.13—Heat Straightening Girder Repair Examples ..... 7-46

Table 7.14—Girder Crack Epoxy Injection Examples ..... 7-48

Table 7.15—Prestressed Concrete Girder Repair (Near Supports) Examples ..... 7-48

Table 7.16—Girder Impact Repair Examples ..... 7-49

Table 7.17—Girder Strand Splice Repair Examples ..... 7-49

Table 8.1—Design Frequency and Allowable Spread of Storm Water ..... 8-2

Table 9.1—Deck Thickness based on Effective Length ..... 9-1

Table 9.2—Deck Thickness for NU Girders ..... 9-1

Table 9.3—Deck Reinforcement ..... 9-2

Table 10.1—Pile Lateral Load Capacities based on Soil Capacity ..... 10-3